


I-15 Reconstruction Project: Innovative Foundation and Embankment Construction



Steven F. Bartlett, Ph.D., P.E.
Assistant Professor
University of Utah



I-15 Reconstruction – Project Extents



**End
Project
600 N.**

Beg. Project 10600 S.

I-15 Reconstruction - Quick Facts

- **Single Largest Design-Build Highway Contract in U.S.**
- **17 Miles of Urban Interstate**
- **\$1.5 Billion (Project Cost)**
- **Wasatch Constructors (Prime Contractor)**
 - **Kiewit, Granite, Washington Construction**
- **4 Year Construction Duration (1997 - 2001)**
- **144 Bridges/Overpass Structures**
- **160 Retaining Walls (mostly MSE Walls)**
- **Approximate \$6 M Research Program (4 years)**

Geotechnical Issues

- **Large Primary Consolidation Settlement (1 to 1.5 m)**
- **Time Rate of Consolidation (2 years to end of primary)**
- **Creep Settlement (Bump at Bridge)**
- **Foundation Stability (Large Embankments on Soft Soils)**
- **Schedule Constraints (two 2-year projects)**
- **Maintenance of Traffic (Had to be maintained)**
- **New Technologies and Development of Specifications**

Selected Topics



PV Drains



Surcharging



Geotextile Reinforced Slopes

Selected Topics (cont.)



2-Stage MSE Walls



Lime Cement Columns




Geofoam – Light Weight Fill

Quantity and Cost Summary


Embankment or Treatment Type	Approximate Quantity	Average In Place Unit Cost
Earthen Embankment	5,00,000 m ³	\$9 / m ³
Pre-fabricated Vertical Drains	7,400,000 m	\$1.50 / m (without pre-drilling) \$3.00 / m (with pre-drilling)
High Strength Geotextile	670,000 m ²	\$12 / m ²
Geofoam Embankment (Type VIII)	107,000 m ³	\$60 / m ³ (without wall) \$70 / m ³ (with wall)
Surcharge Fill Removal	500,000 m ³	\$6 / m ³
Slag Light Weight Aggregate	141,000 m ³	\$18 / m ³
Scoria Light Weight Aggregate	50,000 m ³	\$31 m ³
Lime Cement Column Treatment	68,000 m	\$16 / m (0.6 m diameter) \$18 / m (0.8 m diameter)
Mechanically Stabilized Earth (MSE) Walls	160 walls	\$200 / m ² face of wall (one-stage) \$300 / m ² face of wall (two-stage)

Table 1. Foundation treatments and embankment used on the I-15 Reconstruction Project with approximate quantities and unit costs (adapted from Saye et al., 2001).

Subsurface Profile in Salt Lake Valley





Settlement of Soft Clays in Salt Lake Valley




Approximate 2 years of primary settlement


Consolidation Properties



Typical I-15 Embankment Construction



Prefabricated Vertical Drains



**PV Drain Spacing 1.5 to 2.5 m
triangular spacing**



Placement of anchor bar




Installed drain



PV drain pushed into ground


PVD Installation Issues



Mandrel used on the I-15 Project

1. Consolidation times need to be reduced to 3 to 6 month to accommodate schedule
2. Large, atypical mandrels and anchor plates may cause excessive disturbance and reduce time rate of consolidation
3. PV drains spaced too closely together may cause disturbance and reduce time rate of consolidation
4. PV drain contractor may not be able to push drains through existing embankment

Rate of Consolidation Vs. Drain Spacing



Pre-drilling of PV Drains Required through Existing Embankment



Cost:

\$1.50/ m (without predrilling)

\$3.00/m (with predrilling)

Approximate 3 drill rigs req'd for one PV drain rig

PV Drain Summary


- 1. PVDs reduced settlement to 3 to 6 months and were the key component to I-15 success.**
- 2. PVDs performed as expected.**
- 3. Size and geometry of installation mandrel and anchor plate should be controlled by specification.**
- 4. PVDs should not be spaced closer than 1.5 m triangular spacing for Lake Bonneville Deposits**
- 5. Predrilling was required for installation through large (8 m high) preexisting embankments.**

Surcharging to Reduce Settlement




5 million cubic meters of embankment placed on project

Model for Secondary Consolidation



Surcharging to Reduce Settlement



Amount of Surcharge


Surcharging Summary

- 1. Design goal was to reduce secondary settlement to 3 inches or less in 10 years.**
- 2. Post construction monitoring has shown that surcharging has been successful in achieving this goal.**
- 3. Surcharges of 30 to 40 percent of the final embankment height were used.**
- 4. Large surcharged fills introduced stability concerns in some locations.**
- 5. Surcharge were to remain in place until 98 percent EOP consolidation was reached.**

Geotextile Installation in Reinforced Slopes



Geotextile placement on sloped, pre-existing embankment



Geotextile lapped into MSE wall

Stability Criteria for Reinforced Slopes


Stability Parameter	Threshold Level 1	Threshold Level 2	Threshold Level 3
Horizontal Displacement Rate (mm/day)	3.8 - 7.6	7.6 - 25.0	> 25.0
Displacement Ratio (DR)	0.2 - 0.3	0.3 – 0.4	> 0.4
Piezometric Head Increase	-----	> 200% of Load due to Fill Placement	same as threshold 2
Response Action	<ul style="list-style-type: none"> • Notify Field Construction Manager of threshold 1 • Increase Monitoring Frequency 	<ul style="list-style-type: none"> • Stop Fill Placement • Prepare Specific Action Plan • Implement Plan if Conditions Worsen 	<ul style="list-style-type: none"> • Buttress Slope and Remove Fill • Notify Senior Project Management • Notify UDOT

Stability Criteria -Displacement Ratio

**DR = horz. Displacement
/ vert. settlement**

**Horz. displacement from
Vertical inclinometers**

**Vert. Settlement from
Settlement plates**



Stability Summary

- 1. Large embankments with surcharge introduced foundation stability issues at many bridge crossings.**
- 2. No embankment failures occurred on the project.**
- 3. High strength geotextile (max. 3 layers) was used to achieve global stability with a FS of 1.3.**
- 4. Staged construction was used in many locales to reduce geotextile requirements.**
- 5. Vertical inclinometers and settlement plates were used to monitor stability**
- 6. Stability criteria based on the displacement ratio (DR) proved to be the most useful means of monitoring embankment stability.**

2-Stage MSE Walls



Right-of-way constraints required many slopes to be built vertically.



Beginning of 2-stage MSE Wall

2-Stage MSE Wall Connections



Attachment of Panels with threaded rod



Female threaded rod coupler



**Concrete
Fascia Panel**

MSE Wall Settlement and Deformation Issues




Settlement Impacts to Adjacent Structures



Deformation of Welded Wire Face at Toe of Wall

3500 South MSE Wall Array



Objectives of MSE Wall Arrays

1. Monitor Stress and Strains within Wall and Foundation
2. Determine Settlement Distribution Away from Wall
3. Monitor Transitions Zones
4. Deformation Modeling

UTAH STATE AGGIES



Strain Gauges on Welded-Wire Reinforcing



Horizontal reinforcing (bar mat) with strain gages.



Strain gage wiring at face of MSE wall

3500 South MSE Wall Array




**Inclinometer and Sondex
Locations**



**Reading of Sondex
Extensometer**

3500 S. MSE Wall Deformations



MSE Wall Summary

- 1. Large primary consolidation settlement req'd use of two stage MSE wall with flexible wire face.**
- 2. Flexible faces can deform during construction and post-construction.**
- 3. Increasing the horizontal reinforcement in the bottom half of the wall can reduce the deformation, but not completely eliminate it (horizontal buldge reduce by a factor of 2.)**
- 4. Material type, compaction and construction procedures can also help in reducing face deformation.**
- 5. Specifications should be written to control allowable face deformation.**
- 6. Zone of settlement influence is 1.5 times wall height.**


Geofoam Embankment For Settlement Reduction

**Buried
Utilities**




**Geofoam Embankment from State St. to 200 W. Along
Interstate I-80, Salt Lake City, Utah**

Geofoam Placement Areas



100,000 cubic meters of Geofoam

Geofoam Cross Section (Typical)



Geofoam Properties

Physical Property	ASTM Test Procedure	Type VIII Accepted Value	Type II Accepted Value	Tolerances
Density	D1622	18 kg/m ³	22 kg/m ³	± 10 %
Compressive Resistance	D1621	90 kN/m ²	104 kN/m ²	minimum @ yield or 10 percent axial deformation
Flexural Strength	C203	208 kN/m ²	276 kN/m ²	Minimum
Water Absorption	C272	3	3	< % by volume

Table 2. Properties of Type VIII Geofoam Specified for the Reconstruction I-15 Project.

*** I-15 used 1.25 pcf density exclusively (i.e., type VIII geofoam)**

Geofoam Embankment



**Leveling Course of Sand
for Geofoam Embankment**



**Construction of Geofoam Embankment
and Footing for Tilt-up Panel Wall**

Geofoam Embankment



Nearly Completed Geofoam Embankment with Vertical Face

Geofoam cut and placed around piling at bridge abutment



Transition Zone with MSE Wall

Load Distribution Slab Atop Geofoam



**Reinforced Concrete
Load Distribution Slab
atop Geofoam**




Completed Load Distribution Slab

Geofoam (Finished Cross Section)




Geofoam for Rapid Construction

Comparison of Construction Times




Geofoam Wall Costs



Geofoam wall system (total cost) is about 2 ¼ times more expensive than conventional 2-Stage MSE wall with PV drains

3300 South Geofoam Array



Objectives of Geofoam Arrays

- **Measure Creep Settlement of Geofoam Mass (10 yr.)**
- **Measure the Pressure Distribution within Mass**
- **Measure Differential Settlement in Transition Zones**
- **Measure Lateral Earth Pressure at Abutments**
- **Monitor for Differential Icing at Geofoam / Embankment Transition Zones**
- **Model Stress / Strain Behavior**



3300 South Geofoam Array Installation



**Magnet Extensometer and
Pressure Cell Installation**



Pressure Cell in Base Sand




Pressure Cell Cast in Bridge Abutment



First Method of Placing Pressure Cell

Improved Method of Placing Pressure Cell





Hot Wire Cut



Pressure Cell Placed in Cut

3300 South Magnet Extensometer Data



1% Construction Strain

- ◇ Level 0
- △ Level 2
- Level 4
- Level 6
- Level 8
- + Level 9
- Load Distribution Slab placed
- Load Distribution Slab Curb placed
- ▲ Granular Borrow
- Green Grouted Base

100 South Magnet Extensometer Data Post-Construction Settlement





Figure 37 – Projected settlement trend for I-15 geofoam at 100 South.

3300 South Geofoam Array

Damage to Connections During Construction Loading



Damaged Connection


- Approximately 1% loading strain can be expected.
- Strain due to seating of untrimmed block and elastic compression.
- Damaged connection was later repaired by dowels.
- Rigid connect should be avoided.

Geofoam Transition Zones

Post-Construction Settlement





Transition slope
3.5 H : 1 V



Geofoam Pressure Cell Measurements

Pressure Versus Time
3300 South Street Geofoam Array



Geofoam Conclusions

- 1. Geofoam fills are performing as expected with no major issues.**
- 2. Approximately 1 percent vertical strain occurred during construction.**
 - a. Strain due to seating and compression of geofoam.**
 - b. This strain can damage rigid connections.**
- 3. Approximately 0.2 percent creep strain (15 mm) has occurred in a 2-year post construction period.**
- 4. The vertical stress distribution that develops in a geofoam wedge fill is complex, but generally diminishes with depth.**
- 5. Pressure cell measurements suggest that approximately 45 kPa of vertical stress has developed in the center of the geofoam mass. This is approximately 50 percent of the compressive strength of the geofoam.**

Geofoam Conclusions (cont.)

- 6. Creep strain will be relatively small for dead loads that are less than 50 percent of the compressive strength.**
- 7. Creep strain in a 10 year post-construction period is expected to be 0.25 to 0.3 percent (18 to 21 mm).**
- 8. Transition zones with the MSE wall need to be designed carefully to minimize differential settlement in the transition zone**

Lime Cement Stabilized Soil



Lime Cement Column Rig




**Auger / Mixer for Lime
and Cement**


125 kg/m³ 15% lime 85% cement

M = 30 Mpa (design); Su 300 to 400 kPa


Lime Cement Treatment Area



Lime Cement Column Installation Pattern



Lime Cement Column Installation X-Section



1-Stage MSE Wall Construction




1-stage MSE placed over columns



Finished MSE wall

Lime Cement Column Array



Objectives of Lime Cement Column Array



- 1. Determine the Primary Consolidation**
- 2. Measure the Primary Settlement in the Treated Area and at adjacent structure**
- 3. Measure the Secondary Settlement over 10 yr. Period**
- 4. Determine the Modulus of Treated Area versus Untreated Ground**
- 5. Measure the Shear Strength of the Treated Ground**
- 6. Model the Construction and Long-Term Deformation Behavior**

Pressure and Settlement Cells at Lime Cement Column Array





**Pressure and Settlement Cells
Atop Column**

Horizontal Inclinerometers




Horizontal Inclinerometer Systems, with and without dead-end pulley assembly


Borehole Magnetic Extensometer




Fill Height vs. Load on Lime Cement Columns



Stress ratio = 10:1





Inclinometer Measurements at LCC Array





Ground Settlements at LCC Array

(July 98 to November 01)





Magnetic Extensometer Measurement



23 cm of settlement at magnet extensometer location w/ 12 cm of settlement below column installation depth

Horizontal Displacements from Vertical Inclinometer



LCC Construction Performance


- 1. Primary Consolidation Settlement was reduced from about 1.0m to 0.2 m at LCC array.**
- 2. Construction Settlement of about 18 cm occurred at MSE wall face.**
- 3. Construction Settlement of about 3 to 4 cm occurred at nearby bldg.**
- 4. Lateral Displacement of about 4 cm occurred at wall face.**
- 5. Column is carrying about 10 times the stress as the adjacent untreated ground.**
- 6. Installation rates and cost became an issue with Wasatch Constructors and this technology was only used at one location.**

Long-Term Array Locations


<u>Location</u>	<u>Type</u>
I-80 @ 300 W.	MSE Wall on Lime Cement Columns
I-15 @ 3300 S.	Geofoam Wall (Creep & Load)
I-15 @ 3500 S.	MSE Wall (Deformation & Settlement)
I-15 @ 200 S.	MSE Wall (Settlement)
I-15 @ S. Univ.	Embankment (Settlement)
I-80 @ W. Temple	MSE Wall (Lt. Weight Backfill)
I-15 @ 800 S.	Geofoam (Lateral Earth Pressure)
I-15 @ 100 S.	Geofoam (Differential Icing)
I-15 @ 2100 S.	Embankment (Settlement)
I-15 @ 400 S.	Embankment (Settlement)

Questions

UTAH STATE AGGIES



UTAH UTES



Bartlett@civil.utah.edu



SYRACUSE ORANGEMEN